



- NOTES:
- CONTRACTOR IS RESPONSIBLE FOR ACQUIRING AND MAINTAINING STORM WATER PERMITS. EROSION CONTROL BEST MANAGEMENT PRACTICES SHALL BE INSTALLED & MAINTAINED AS REQUIRED BY PERMIT.
 - PROVIDE GRASSING IN ALL DISTURBED AREAS AS SPECIFIED.
 - CONTRACTOR SHALL SOD ALL DITCHES & SWALES.
 - CONTRACTOR SHALL SOD ALL DISTURBED SLOPES THAT ARE 4:1 OR GREATER.
 - CONTRACTOR SHALL SOD ALL AREAS WITHIN 12' OF ALL BUILDINGS AND CONCRETE STRUCTURES, AND SOD ALL AREAS WITHIN 4' OF SIDEWALKS AND PAVING.
 - SOD SHALL BE CENTIPEDE, FREE OF WEEDS AND OTHER UNDESIRABLE GRASSES. CONTRACTOR SHALL SECURELY ANCHOR SOD TO THE GROUND IN REQUIRED AREAS.
 - ALL DISTURBED, NON-PAVED AND NON-SODDED, AREAS TO BE GRASSED AS SPECIFIED.



SITE / GRADING PLAN
SCALE: 1" = 20'-0"

NO.	ELEV. / LOCATION
1	FIN. FL. EL. 122.57 / CONTROL BLDG. PAD
2	FIN. FL. EL. 122.50 / BLOWER PAD
3	FIN. FL. EL. 122.50 / DIGESTER PAD
4	FIN. FL. EL. 130.00 / DIGESTER WALKWAY
5	TOP OF WALL EL. 133.50 / DIGESTER BASIN
6	FIN. FL. EL. 122.50 / DIGESTER STAIRS BOTTOM LANDING
7	FIN. FL. EL. 146.50 / SCREEN PLATFORM
8	FIN. FL. EL. 142.00 / SBR BASIN WALKWAYS
9	FIN. FL. EL. 122.50 / SBR BASIN SLABS
10	TOP OF WALL EL. 145.50 / SBR BASINS
11	FIN. FL. EL. 134.50 / SBR STAIRS INTERMEDIATE LANDING
12	FIN. FL. EL. 122.50 / SBR STAIRS BOTTOM LANDING
13	FIN. FL. EL. 122.50 / EQ BASIN SLAB
14	TOP OF WALL EL. 134.00 / EQ BASIN
15	FIN. FL. EL. 130.50 / EQ BASIN WALKWAY
16	FIN. FL. EL. 122.33 / EQ BASIN STAIRS BOTTOM LANDING
17	FIN. FL. EL. 119.50 / FILTER SLAB
18	FIN. FL. EL. 122.50 UV. SLAB